

7" PACKAGE ROOM PANEL

(see pages 2 and 3 for measurements)



TOUCHSCREEN

- Brightness : 1000 Nits
- Diagonal length: 7"
- Resolution: 1024 x 600
- Contrast ratio : 700:1
- Capacitive touch
- IP65 dust and water resistance
- Chemical resistant/ Anti-glare coated



- Bluetooth connectivity
- Touch screen withstands a 225g drop ball test from 1.6 meters
- Designed for standard power socket: NEMA 5-15
- Max temperature: +60° C/+140° F



DIMENSIONS

- 12.44" x 7.539" x 2.027"
- 316.0mm x 191.5mm x 51.5mm



POWER REQUIREMENTS

- Panel input voltage: 24VDC
- Standard power consumption: 31W at 24VDC input
- Maximum power consumption: 65W at 24VDC input
- Relay max switching current: 5A, relay max switching power: 1250W
- No AC power directly connected to panel
- Coordinate dedicated electrical circuit on UPS (power conditioned)





- 2 Mbps ethernet connection Cat5e/Cat6
- No WiFi
- No DSL
- IP assigned by DHCP by default for static IP assignment call support
- 4G SIM card is supported (refer to building network requirements for details)



- For camera angle adjustment, call support
- For the installation of the backplate, M4 countersink screws will be needed (not provided)

Support:

P: (800) 398-4416 ext. 2 (Mon-Fri, 6am-10pm EST)

E: support@butterflymx.com


v1-2022-12-06 Page: 1 of 3




SCALE: Not to scale


SUPPORT: P: (800) 398-4416 ext. 2 (Mon-Fri, 6am-10pm EST) E: support@butterflymx.com

DRAFT SUBJECT TO CHANGE VERSION: v1-2022-12-06 **PAGE:** 2 of 3







PANEL REAR w/ BACKPLATE 6 NOT TO SCALE




PANEL REAR ELEVATION


















The following plans are diagramatic. It will be up to the installation contractor to coordinate with associated trades to formalize a complete submission for installation. Panel mounting height to be ADA Compliant.





ADA Compliance Requirement







The following plans are diagramatic. It will be up to the installation contractor to coordinate with associated trades to formalize a complete submission for installation. Panel mounting height to be ADA Compliant.